

Task Order 1005

Issued By:	Independent Programme Director	Issued To:	Bath and North East Somerset
Product Title:	A4 Twerton Fork		
Start Date:	October 2007	Completion Date:	February 2008
Product Aim:	To provide additional priority to buses, particularly during the evening peak, at the signalised junction of the A4 and A36 west of Bath city centre (Twerton Fork).		
Product Description:	<p>Following public consultation and subject to direction from the Independent Programme Director (IPD), to undertake the design, statutory processes, procurement and installation of a bus detector loop. The loop is to be placed on the westbound lane of the A4 approaching Twerton Fork, approximately 360m prior to the junction.</p> <p>An indicative design drawing is attached (see C03-004).</p> <p>The following tasks are to be undertaken:</p> <ul style="list-style-type: none"> - Detailed design of scheme elements including: <ul style="list-style-type: none"> • location of bus detector loop • DUCT between detector loop and signalised junction - Statutory consultation as necessary - Design amendments as necessary - Appointment of contractor - Finalise costs and scheme design, reporting any changes to the IPD - Manage installation 		
Deliverables:	<ul style="list-style-type: none"> - Detailed scheme drawings in accordance with task description - Bill of Quantities for scheme construction - Detailed cost schedule based on Bill of Quantities - Detailed construction programme - Environmental assessment - Non-Motorised User (NMU) Audit - Traffic Management Strategy for construction period - NRSWA public utilities search (expires after 6 months) and liaison with public utility companies - Schedule of public utility protection and diversion works - Brief for Stage 1 & 2 RSA - Acceptance and Exception Report for each RSA - Scheme delivery - Final report to IPD detailing delivery and outturn costs 		
Assumptions	<ul style="list-style-type: none"> - All design processes will be in accordance with the GBBN Project Handbook. 		

Quality Checking Arrangements Work to be done in accordance with standards set out in GBBN Project Handbook and Project Quality Plan		Configuration Management Requirements Any change to this Works Package Task Order, associated design, budget and timescale, should be in accordance with the procedures outlined in the GBBN Project Handbook.	
Reporting Arrangements Regular reporting on progress required (including design, procurement, current spend against profiled, and current implementation timetable against profiled). Details set out in GBBN Project Handbook.			
Implementation Programme: Target – Preparation works commence: October 2007 Target – Construction works commence: February 2008 Target – Construction complete: February 2008			
Resources (Estimate): Design staff resource (days): <i>(Enter)</i> Design consultation staff resource (days): <i>(Enter)</i> Other staff resource: <i>(Enter)</i>			
Budget (inc. Inflation): Total budget: £51,000		Tolerances:	
Contact for further information: Independent Programme Director			
Above details agreed	<i>Independent Programme Director</i>		
	Name:		
	Signed:		
	Date:		
	<i>Unitary Authority Project Manager</i>		<i>Unitary Authority Task Manager</i>
	Name:		Name:
	Signed:		Signed:
	Date:		Date: